


ACTUAL SIZE



NOTES:

1. ALL DIMENSIONS ARE IN INCHES [MILLIMETERS].
2. SLEEVE MATERIAL: RYNITE FR530
3. BASE MATERIAL: NICKEL PLATED BRASS
4. OPERATING TEMPERATURE: ~ -30°C TO ~ +50°C

**FULL BEAM WIDTH AT 50% INTENSITY

REVISION NOTIFICATION

- ☐ DLC
- ☐ UL/ETL
- ☐ MADE IN USA
- ☐ CUSTOMER _____
- ☐ OTHER _____

REDLINE CHECKLIST

- ☐ REDLINE(YES)
- ☐ DATE: _____
- ☐ INITIATED BY: _____
- ☐ ECR REQUIRED YES ☐ NO ☐
- ☐ WORK ORDER# _____

ELECTRICAL-OPTICAL CHARACTERISTICS (Ta = 25°C)

F206-0UG-120A	—	SUPER LIME GREEN	120Vac	0.46 W	0.006 A	0.090 cd	570nm	160°
F206-0UY-120A	—	SUPER YELLOW	120Vac	0.43 W	0.006 A	0.110 cd	595nm	160°
F206CG6-0006	F206CG6-120Vac/8	HI-EFF GREEN	120Vac	0.40 W	0.006 A	0.037 cd	565nm	160°
F206C06-0009	F206C06-120Vac/8	ORANGE	120Vac	0.72 W	0.006 A	0.015 cd	608nm	160°
F206CPG6-0010	F206CPG6-120Vac/8	PURE GREEN	120Vac	0.63 W	0.006 A	0.007 cd	557nm	160°
F206CR6-0003	F206CR6-120Vac/8	HI-EFF RED	120Vac	0.64 W	0.006 A	0.022 cd	633nm	160°
F206CY6-0017	F206CY6-120Vac/8	YELLOW	120Vac	0.48 W	0.006 A	0.015 cd	585nm	160°
LEDTRONICS PART NO.	DESCRIPTION PART NO.	COLOR EMITTED	INPUT VOLTAGE, V	POWER (W)	CURRENT (A)	MAXIMUM CANDELA	λP nm	VIEWING ANGLE**

LED[®]
LEDTRONICS,™ INC.
 23105 KASHIWA COURT
 TORRANCE, CA 90505

-PROPRIETARY-
 This document contains Proprietary
 information of LEDTRONICS, INC.
 It may not be copied, used or disclosed
 for any purpose without the prior express
 written consent of LEDTRONICS, INC.

.XXX ± .010 TOLERANCE PER ANSI-Y14.5
 .XX ± .025 (UNLESS OTHERWISE STATED)
 ANGLES ± 0°.30'
 FRACT. ± 1/32

TITLE

F206CXX6-00XX
(F206CXX6-120VAC/8)

DWG NO

F206-120VAC

SCALE

2:1

SHEET

1 OF 1

DATE

03-04-15

CODE
 IDENT NO.
 8Z410

DWG BY
 GP
 03-04-15

CHK BY

QA
 SB
 03-05-20

MFG
 LD
 03-05-20

R&D
 UF
 03-05-20