




ACTUAL SIZE



NOTES:

1. ALL DIMENSIONS ARE IN INCHES [MILLIMETERS].
2. SLEEVE MATERIAL: RYNITE FR530
3. BASE MATERIAL: NICKEL PLATED BRASS
4. OPERATING TEMPERATURE: ~ -30°C TO ~ +50°C

**FULL BEAM WIDTH AT 50% INTENSITY

REVISION NOTIFICATION

- ☐ DLC
- ☐ UL/ETL
- ☐ MADE IN USA
- ☐ CUSTOMER _____
- ☐ OTHER _____

REDLINE CHECKLIST

- ☐ REDLINE(YES)
- ☐ DATE: _____
- ☐ INITIATED BY: _____
- ☐ ECR REQUIRED YES ☐ NO ☐
- ☐ WORK ORDER# _____

ELECTRICAL-OPTICAL CHARACTERISTICS (Ta = 25°C)

F206-0UR-024V	-	ULTRA RED	24Vdc	0.31 W	0.013 A	0.210cd	663nm	160°
F206-0UY-024V	-	SUPER YELLOW	24Vdc	0.34 W	0.014 A	0.225cd	593nm	160°
F206CG6-0005	F206CG6-24V/20-P	HI-EFF GREEN	24Vdc	0.31 W	0.013 A	0.075cd	566nm	160°
F206CPG6-0007	F206CPG6-24V/20-P	PURE GREEN	24Vdc	0.31 W	0.013 A	0.015cd	557nm	160°
F206CR6-0026	F206CR6-24V/20-P	HI-EFF RED	24Vdc	0.34 W	0.014 A	0.045cd	632nm	160°
F206CY6-0004	F206CY6-24V/20-P	YELLOW	24Vdc	0.34 W	0.014 A	0.030cd	584nm	160°
LEDTRONICS PART NO.	DESCRIPTION PART NO.	COLOR EMITTED	INPUT VOLTAGE, V	POWER (W)	CURRENT (A)	MAXIMUM CANDELA	λP nm	VIEWING ANGLE**

LED[®]
LEDTRONICS,™ INC.
 23105 KASHIWA COURT
 TORRANCE, CA 90505

-PROPRIETARY-
 This document contains Proprietary
 information of LEDTRONICS, INC.
 It may not be copied, used or disclosed
 for any purpose without the prior express
 written consent of LEDTRONICS, INC.

.XXX ± .010 TOLERANCE PER ANSI-Y14.5
 .XX ± .025 (UNLESS OTHERWISE STATED)
 ANGLES ± 0°.30'
 FRACT. ± 1/32

TITLE

F206-0UX-024V
F206CXX6-00XX

DWG NO

F206-24V-P

SCALE

2:1

SHEET

1 OF 1

DATE

02-20-07

CODE
 IDENT NO.
 8Z410

DWG BY
 GP
 02-20-07

CHK BY

QA
 SB
 03-03-20

MFG
 LD
 03-03-20

R&D
 UF
 03-03-20